

HEALTH & SAFETY POLICY

**Total Construction Limited
The Old Courtyard
Copthall Farm
Breakspear Road South
Ickenham
Middlesex
UB10 8HB
Tel: (01895) 672672
Fax: (01895) 672670**

CONTENTS

SECTION 1 POLICY STATEMENT

SECTION 2 INDIVIDUAL RESPONSIBILITIES

SECTION 3 ARRANGEMENTS

- 3.1 Training and Education
- 3.2 Monitoring of Safety Performance
- 3.3 Safety Inspection Reports
- 3.4 Consultation with Employees and Sub Contractors
- 3.5 Reporting of Accidents and Dangerous Occurrences
- 3.6 First Aid and Welfare Requirements
- 3.7 Fire Precautions and Emergency Procedures
- 3.8 Risk Assessments
- 3.9 Electricity
- 3.10 Work Equipment
- 3.11 Personal Protective Equipment
- 3.12 Below Ground Works
- 3.13 Confined Spaces
- 3.14 Lifting Operations
- 3.15 Site Traffic Management
- 3.16 Work in Occupied Premises

SECTION 4 SAFETY MANAGEMENT SYSTEM

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 2 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

SECTION 1 POLICY STATEMENT

- 1) It is the Company's policy that its operations shall be conducted in such a way as to ensure, so far as is reasonably practicable, that the health, safety and welfare of its employees and of any other person who may be affected by its operations are protected. This policy will be actively pursued by the Directors and Managers and the company is committed to the prevention of injury and ill health.
- 2) The Company requires that a high standard of safety, health and welfare shall be achieved and consistently maintained both on site and at the Company's offices.
- 3) It is imperative that every employee familiarises him or herself with the content of this policy. Its effectiveness can only come from the combined efforts of us all. We expect every employee to give their full commitment and cooperation to the implementation of this policy.
- 4) The Company acknowledges the fact that safety and operational efficiency are complementary and that the use of safe working practices and accident prevention techniques are a most important responsibility of management.
- 5) The requirements of the Health and Safety at Work etc. Act 1974, and the Management of Health and Safety at Work Regulations 1999 and all legislation relevant thereto shall be regarded as the minimum standard of health, safety and welfare to be achieved and the company will comply with all legal and other identified requirements relating to its Occupational Health and Safety (OHS) hazards.
- 6) This company will allocate sufficient resources to enable the Policy to function effectively. An annual review shall be conducted to determine the resources required to implement this policy. Planning and organising is an ongoing activity within the business. Our procedures are certificated to OHSAS 18001 and are continually reviewed in order to ensure continuous improvements to our procedures and performance. The reviews shall identify the human and financial resources required to implement our policy.
- 7) Protective clothing and equipment shall be made available to employees, and shall be used by all employees when the nature of the work being carried out requires the use of such protective gear in the interests of health and safety. Personal Protective Equipment (PPE) shall only be used as a workplace precaution and as the last resort.
- 8) All employees shall be encouraged to submit suggestions and ideas for improving the general standards of health, safety and welfare.
- 9) Employees have a duty under Section (7) of the Health and Safety at Work etc Act 1974 to take reasonable care for their own safety and the safety of any other person who may be affected by their acts or omissions and also to co-operate with the Company in its arrangements to perform or comply with statutory safety obligations which include adherence to the Company's Safety Policy.
- 10) All employees, regardless of status, found to be deliberately and consistently negligent in their performance of the Company's Policy on Health, Safety and Welfare may be subject to instant dismissal.
- 11) This Policy will be reviewed annually or revised and updated when new legislation or guidance is introduced.

Signed

Guy T Butler

Managing Director

Date: 12th April 2016

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 3 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

HEALTH & SAFETY POLICY

REVIEWS

Reviews of the Health and Safety Policy shall be carried out annually by the Managing Director and the Safety Advisor.

Review Date	Reviewed by
Jan 2010	G Butler/ M Bolland
Jan 2011	G Butler/M Bolland
Oct 2011	G Butler/M Bolland
Dec 2011	G Butler/M Bolland
Feb 2012	G Butler/M Bolland
May 2012	G Butler/M Bolland
July 2013	G Butler/M Bolland
October 2013	G Butler/M Bolland
January 2014	G Butler/M Bolland
April 2014	G Butler/N Baker/M Bolland
April 2015	G Butler/N Baker/M Bolland
April 2016	G Butler/N Baker/M Bolland

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 4 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

SECTION 2 INDIVIDUAL RESPONSIBILITIES

2.1 Managing Director

- a. Shall require a positive approach to Safety at all management levels.
- b. To ensure that staff receive adequate Health and Safety education and training commencing with induction training.
- c. Maintain the Company's Safety Policy on a progressive basis, ensuring that the methods of accident prevention and internal procedures are kept up to date.
- d. Maintain close contact with our health and safety advisors.
- e. Know the requirements of the Health and Safety at Work etc Act 1974, and all other relevant statutory requirements; this will be achieved via briefings, and newsletters from our safety advisors.
- f. Set a personal example during monitoring inspections by following safe working practices and recognising and praising positive behaviours.

2.2 Duties of Directors and Other Senior Managers

Shall implement this Policy by:-

- a. Making full provision for safe methods of working and adequate welfare facilities at the tender stage on all contracts.
- b. Ensuring the Health and Safety at Work etc. Act 1974, the Management of Health and Safety at Work Regulations 1999 and the CDM Regulations 2015 are followed and the necessary health and safety plans, risk assessments and method statements are produced and brought to the attention of the relevant people.
- c. Ensuring staff at all levels receive appropriate training.
- d. Monitoring health and safety performance through site meetings, reacting to safety adviser reports, and responding to actual site conditions observed when on routine site inspections.
- e. Holding regular meetings with employees and other site operatives to receive comments and suggestions on ways in which health and safety performance can be improved.
- f. Liaising with the Health and Safety Advisor and taking charge of problems which cannot be adequately controlled/concluded at site level, especially with regards to control of sub-contractors.
- g. Setting a good personal example and having adequate knowledge of health and safety legislation relating to our work.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 5 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

2.3 Duties of Site Managers (and other persons in control of the site)

The duties are to:

- a. Understand the Total Construction Ltd Health and Safety Policy and ensure it is brought to the attention of all employees, particularly new starters, through induction talks if necessary.
- b. Have adequate knowledge of, and observe the requirements of the construction regulations and other legislation and codes of practice; ensuring that all statutory registers and records are maintained and that persons under your control are adequately trained to enable them to carry out their duties.
- c. Ensure that the necessary risk assessments have been carried out and recorded and that detailed method statements adopting “best working practice” approach is used for high risk activities.
- d. Ensure that adequate arrangements are made with regards to fire precautions, first aid equipment trained first aiders or appointed persons, and the procedures, to be followed in an emergency are all in place.
- e. In planning the site layout and work, make adequate provision for welfare facilities. Organise the site so that work carried out to the correct standard with minimum risk to operatives and other persons, equipment, materials, and members of the public, both during and outside site hours. Encourage employees to be pro-active in developing a positive approach to health and safety performance.
- f. Carry out (or arrange for others to carry out) site induction talks for new arrivals onto site.
- g. Ensure any accident or incident is reported in accordance with Total Construction Ltd Safety Management System.
- h. Set a good personal example at all times.

2.4 Duties of Site Manager and Staff Visiting Site

The duties are to:

- a. Be familiar with the Total Construction Ltd health and safety policy and the legislation as it relates to their work.
- b. Ensure that precise instructions are given to operatives, detailing what precautions/actions must be taken to minimise risk.
- c. Ensure that new employees, apprentices, young persons or occasional site workers are aware of the dangers and what precautions they must take.
- d. Report any defects in plant, equipment, scaffolding, excavations etc. to the site manager together with details of any dangerous practices observed on the site.
- e. Set a good personal example and ensure small plant, tools and equipment are being used correctly.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 6 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

2.5 Duties of the Health and Safety Advisor

To encourage a pro-active approach to health and safety matters and a positive attitude to risk management functions.

- a. To keep themselves up to date with current legislation and best working methods and to disseminate this information throughout the company. At all times they must be prepared to assist management in whatever way they can with regards to health and safety.
- b. With regards to sites, they should carry out regular inspections and report on their findings. In addition they should assist the Contracts Manager and site manager by advising on working methods and training requirements. They should be available, when requested, to attend planning meetings.
- c. To assist the Managing Director, the Safety Advisor shall produce an annual report commenting on the performance of the previous period and assist in setting objectives for the next period.
- d. If in their opinion they are confronted with a risk of imminent danger to life, then they should take whatever action they consider necessary and report the occurrence and action taken to the Contracts Manager, and if need be, the Managing Director.

2.6 Duties of Office Management

Your duties are to

- a. Understand the Total Construction Ltd health and safety policy and ensure it is brought to the attention of all employees, particularly new employees and temporary employees, through induction talks.
- b. Have adequate knowledge of the Health and Safety at Work etc. Act 1974 and those persons under your control are adequately trained to enable them to carry out their duties.
- c. Ensure that adequate arrangements are made with regards to fire precautions, first aid equipment, trained first aiders or appointed persons, and the procedures, to be followed in an emergency are all in place.
- d. Ensure that adequate arrangements are made for employees using Display Screen Equipment (DSE) with regards to workstation, rest periods, etc.
- e. Ensure that adequate arrangements are made for the provision for welfare facilities.
- f. Carry out (or arrange for others to carry out) induction talks for new employees or temporary employees.
- g. Ensure any accident/incident is reported in accordance with Total Construction Ltd Safety Management System.
- h. Set a good personal example at all times.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 7 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

2.7 Duties of all Site Staff and Operatives

The Health and Safety at Work etc. Act 1974 requires all employees and self employed persons to take reasonable care of themselves and others who may be affected by his/her acts or omissions, and to co-operate with Total Construction Ltd by observing Total Construction Ltd's procedures and so enabling the company to comply with its statutory duties.

In particular, you can assist by:

- a. Taking a pro-active role in assessing Total Construction Ltd's health and safety performance and suggesting ways (via your manager) in which improvements can be made.
- b. Using the appropriate protective equipment (i.e. head protection, eye protection, hearing protection, safety footwear, high visibility waistcoat or jacket etc.) if required for the job.
- c. Keeping personal tools and equipment in good condition.
- d. Reporting all defects in plant, equipment, together with any unsafe acts to your immediate supervisor.
- e. Not operating any plant or carrying out any task for which you have not been trained or are unfamiliar.
- f. It is important that you feel capable of doing the task in which you are involved. If you have any doubt you should inform your immediate supervisor.

DO NOT TAKE CHANCES.

THINK WHAT IF, NOT IF ONLY

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 8 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

SECTION 3 ARRANGEMENTS

3.1 TRAINING AND EDUCATION

Safety education and training is regarded as an indispensable ingredient of an effective health and safety programme. It is essential that every employee in the organisation is trained to perform their job effectively and safely. It is the opinion of the management that if a job is not done safely then it is not done effectively.

All employees will be trained in safe working practices and procedures upon commencement of employment and prior to being allocated any new role. Training will include information, instruction and advice on the Company procedures and the use and maintenance of personal protective equipment and emergency contingency plans.

Safety training will be provided by experienced training instructors from commercial training providers, e.g. SRM, CITB, Construction Health and Safety Group, etc. The training may be on site or at a commercial training centre. Our commitment to this subject is demonstrated by attendance by employees on the IOSH Managing Safely in Construction & Allied Industries course followed by annual refresher training.

Training records are maintained at Head Office within each individual employee's personal record.

3.1.1 Employees

The Managing Director will carry out an annual review of health and safety training and education needs for all levels of staff. In carrying out the review the Managing Director will pay particular attention to persons whose role has changed, possibly due to a change in their scope of work, or possibly due to legislation. Employees taking on board additional responsibility may need additional training.

The education and training needs will be agreed by the directors and budgets allocated. The Managing Director and Health and Safety Advisor will monitor that the training schedule is completed.

3.1.2 Plant Operatives

All plant operatives will be trained and certificated in accordance with the CPCS training scheme. Additional training will be carried out as required for items such as abrasive wheels, cartridge tools, and other plant and equipment as required. For operatives using mobile tower scaffolds and mobile elevating work platforms they will receive PASMA and IPAF training. Records will be maintained at Head Office.

Subcontractors required to use plant and equipment on site must provide evidence of operator training and procedures for regular testing and inspection of site plant.

3.1.3 Site Induction Training

The site manager (or his delegated representative) will carry out induction training for all new arrivals to site informing them of the significant risks identified in the health and safety plan together with the site emergency and first aid procedures. He will also cover:-

- a. The significant risks and precautions to be taken
- b. The PPE requirements
- c. Where/how to obtain additional PPE as required

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 9 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

- d. Details of site emergency procedures
- e. Details of site welfare arrangements
- f. Details of any method statements relevant to the actual work the person is involved in
- g. The site rules in general

Confirmation of the site induction will be recorded in the induction register.

3.2 MONITORING OF SAFETY PERFORMANCE

The Managing Director, Contracts Managers, site managers and the Health and Safety Advisors have specific responsibility to monitor the implementation of the Total Construction Ltd health and safety policy and to review the company's performance. To assist in this process the annual report produced by the Health and Safety Adviser will cover:

- a. Review of any significant accidents or incidents and identify if a procedural change is required.
- b. Review of any comments from the Health and Safety Executive (HSE), clients or other parties.
- c. Review of last period's safety objectives and determine if they have been achieved.
- d. Review any new legislation, guidance notes, or HSE initiatives.
- e. Review the Safety Management System, working procedures and training requirements, as appropriate.
- f. Set safety objectives for next period.

In addition, the Health and Safety Advisor will carry out routine site inspections to monitor working practices and be available to advise all employees on health and safety issues. As part of the site inspection the Health and Safety Advisor will audit the Total Construction Ltd procedures and will make comment on the findings on the site inspection report.

3.3 SAFETY INSPECTION REPORTS

3.3.1 Procedure During and Following a Health and Safety Advisor Inspection

The Health and Safety Advisor will make routine inspections of the site to monitor working practices and report on his findings. He will also advise the site manager and operatives of any health and safety issues as they arise. As part of the site inspection consideration shall be given to works that are to take place in the coming 4 weeks and to highlight to the site manager and Contracts Manager any information or actions relating to those works.

On completion of the visit, he will produce a written report of his findings. These will be discussed with the site manager who will sign, acknowledging receipt of the report.

The Health and Safety Advisor shall note in the action column on the report what is required with a date by when the action should be completed. As the site manager actions the items raised, he should indicate this in the action column with his initials and the date action was taken. The Health and Safety Adviser will follow up the site inspection report by telephoning the site manager the week after the visit as well as reviewing the report on the next visit to identify any outstanding actions.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 10 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

The Health and Safety Advisor will also send the Contracts Manager a copy of the report for his information with a copy also issued to the Managing Director so that they can monitor the site manager's actions.

If on a subsequent visit the Safety Adviser is of the opinion that adequate action has not been, and will not be taken, he must inform the Managing Director.

If the Safety Adviser is of the opinion that an operation constitutes a risk of serious injury to any person then he will take whatever action he feels necessary. If the site manager disagrees with this action the activity is to cease and the Managing Director is to be informed immediately. The Managing Director will then resolve the issue.

3.4 CONSULTATION WITH EMPLOYEES AND SUBCONTRACTORS

3.4.1 Consultation

Total Construction Ltd has a pro-active approach to health and safety and recognises the benefits of employees having a significant input into the Total Construction Ltd health and safety procedures. They also play a vital role in providing feedback on actual performance, and identifying hazards that may have previously been missed. Total Construction Limited will consult employees in good time on health and safety matters, and in particular:

- When introducing measures which may affect health and safety
- The appointment of competent persons
- The provision of health and safety training
- The health and safety consequences of new technologies

On site all employees (and subcontractors) will receive a site induction. On major sites this will be undertaken by the site manager.

The induction will cover:-

- ◆ Site rules and PPE
- ◆ Welfare facilities
- ◆ First aid arrangements and emergency procedures
- ◆ The significant risks identified in the safety plan
- ◆ Relevant method statements
- ◆ Details of the arrangements for consultation

Throughout the project, all employees and contractors will be encouraged to continually liaise with the site manager to assist in the identification of any health and safety hazards that have not previously been identified.

3.4.2 Consultation with New Employees

The following procedures will be carried out for new employees:

- Explain to the new employee what he/she will be required to do and whom he/she is responsible to.
- Explain where Total Construction Limited's Health and Safety Policy is kept and explain its purpose and ensure the employee is aware of his/her responsibility.
- Ascertain if the employee has any disability or illness, which would affect their duties.
- Advise the employee of any hazards applicable to their works and duties and make them aware of the relevant risk assessments.
- Ascertain any training needs.
- Issue the employee with protective clothing as required.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 11 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

- Inform the employee of the location of first aid equipment on site and advise him/her of the first aider.
- Any sub contractor wishing to bring an employee under the age of 18 on to site must first discuss this with Total Construction Ltd and produce a Young Person's Risk Assessment detailing how they will be kept healthy and safe on site, the limitations placed on their activities and how they will be adequately supervised.

3.4.3 Consultation with Subcontractors

Under the Construction (Design and Management) Regulations 2015, subcontractors have to be competent and Total Construction Ltd has a target of 100% CSCS card holders for site personnel. In addition Total Construction Ltd has to provide details of the significant risks that they will encounter on site. This will be achieved via the project health and safety plan.

When subcontractors are submitting their proposals to Total Construction Ltd they will be asked to provide information about any significant risk their work will produce. These will be subject to an acceptable method statement and, if required an amendment or addition to the project safety plan.

In this way there is an exchange of information before the subcontractor begins work. This flow of information and joint consultation must continue throughout the project. On large multi contractor projects this may require a formal safety meeting with minutes etc. If on a particular project there are only one or two subcontractors working under Total Construction Ltd's control there is generally no need for a formal safety meeting but the site manager should still discuss health and safety matters with the subcontractors and given them an opportunity to comment on the way the site is being run.

3.5 REPORTING OF ACCIDENTS AND DANGEROUS OCCURENCES

There are a number of reasons why it is essential that all accidents/incidents are recorded and where applicable reported. These include:-

- Total Construction Ltd requirement to assist in monitoring health and safety performance.
- Legal requirements to report certain specified injuries, ill-health and dangerous occurrences to the Health and Safety Executive (RIDDOR 2013).
- Insurance company requirements to notify them and keep details for potential claims.
- Department of Social Security requirements to keep details of all accidents in the workplace accident book.

Therefore all accidents and incidents should be recorded in the Total Construction Ltd accident book, no matter how trivial the incident, and for accidents that result in lost time or damage the Total Construction Ltd incident report forms should be completed. Each site manager is responsible for ensuring that any accident involving Total Construction Ltd staff is entered into the accident book and to inform the Managing Director of any such accident.

The following sub sections give detailed guidance on what action should be taken depending on both the nature of the incident and the person who has been injured. Additional guidance can also be obtained from the Safety Management System.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 12 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

3.5.1 Violence to Staff

If a person is injured due to an act of violence sustained whilst at work, and as a result of the injuries the person is unable to work as normal then the incident should be classed as a work accident and actions taken according to the degree of injuries and absence from work.

3.5.2 All Accidents and Incidents

All accidents/incidents which occur on premises under the control of Total Construction Ltd should be entered in the accident book, no matter how trivial and irrespective of whether the injured person is an employee, self-employed, subcontractor or authorised visitor.

3.5.3 Incidents Involving Members of the Public, Visitors and Unauthorised Visitors

If any member of the public, visitor or unauthorised person is involved in an incident or is injured, details must be entered in the accident book and the Total Construction Ltd incident notification form completed. The site manager should also notify the Total Construction Ltd Managing Director as soon as possible. In doing so the site manager should discuss whether a full investigation is required by the Health and Safety Advisor and action accordingly.

If the incident is such that the injured person has to be taken to hospital (by whatever means) the incident must be reported to the Health and Safety Executive by the quickest means (i.e. telephone) and confirmed within 10 days via the HSE's website reporting system.

3.5.4 Incidents Reportable under the Reporting of Injuries Diseases and Dangerous Occurrences Regulations 2013 (RIDDOR)

The Total Construction Ltd Safety Management System (SOP 04) includes detailed guidance on what constitutes a reportable incident under RIDDOR together with a procedure for notification both internally and to the enforcing authorities.

In the event of a serious incident the procedure describes what must be done to ensure that a thorough accident investigation is implemented.

3.5.5 Accident/Incident Investigation

All accidents/incidents shall be investigated by the senior managers supported by the safety adviser with the following objectives:

- To determine the root causes to prevent any recurrence.
- Provide adequate information for reporting under RIDDOR.
- To assist the enforcing authorities in their investigation.
- To provide information to the company's insurers in respect of any compensation claim.

The level of investigation will be determined by the seriousness of the incident but as a minimum shall consider the following:

- The root causes
- Who was involved, including any witnesses
- When did the incident occur
- Why did it occur
- What measures must be taken to prevent a recurrence and if these were already in place why were they not followed

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 13 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

3.6 FIRST AID AND WELFARE REQUIREMENTS

3.6.1 First Aid Box – Site Operations

A standard first aid box of a size appropriate for the numbers on site will be provided at the start of each project. If the site is of a special nature, additional items will be provided as required.

It is Total Construction Ltd policy to have a trained first aider on all sites. In general, this will be the site manager. Notices will be posted indicating the location of the first aid box and the names of the trained first aiders.

3.6.2 Welfare Facilities

The following will be provided as minimum facilities on all sites, where welfare is provide by the client agreement on their use should be obtained.

- ◆ A canteen room with facilities for warming food and boiling water for drinks. Seating with backs will be provided.
- ◆ Facilities for storing and drying clothing and PPE.
- ◆ A toilet unit with facilities for washing. NB on sites with contaminated ground, a shower unit may be required if so this will be detailed in the site health and safety plan.

3.6.3 Drinking Water

An adequate supply of fresh drinking water must be provided. If normal mains running water is not available then a supply of water should be provided via containers which are clearly marked "DRINKING WATER".

3.7 FIRE PRECAUTIONS AND EMERGENCY PROCEDURES

3.7.1 Site Operations

All potential fire hazards will be identified in the initial fire risk assessment and steps will be taken to remove the hazards from site or to minimise the risks. Total Construction Ltd will develop a site fire safety plan that will detail how the risk of fire will be managed for each project. This plan will be reviewed and updated as the project develops. Fire detection and fire fighting equipment shall be made available as early in the project as is reasonably practicable and shall be suitable and sufficient for the nature and complexity of the project. As part of the site control measures the Total Construction Ltd Hot Work Permit shall be used. This shall be issued by the Site Manager before any hot work is permitted on site. Hot works are defined as any work which creates heat, sparks or flames such as cutting, grinding, welding, soldering or brazing. It also includes use of hot air guns whereby the surface temperature of the material being heated may combust.

If sub contractors have to carry out work which increases the risk of fire, then fire extinguishers may be required local to the work area.

The sub contractor doing the work should ensure all loose flammable materials is moved away from the area and have their own suitable fire extinguisher close-by and available for immediate use should the need arise.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 14 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

3.7.2 Emergency Procedures

As Principal Contractor Total Construction Ltd will produce emergency procedures for the project and these will be detailed in the Construction Phase Plan. All employees and contractors will be advised of these procedures via the site induction. If Total Construction Ltd is working as a contractor on a site under the control of a Principal Contractor, then Total Construction Ltd, and their subcontractors, will follow the emergency procedures laid down by the Principal Contractor for that project.

3.7.3 Offices

The Managing Director will ensure that the appropriate number of fire extinguishers together with a fire alarm system is provided. Notices will be posted stating the evacuation procedures together with names of the fire wardens for the various sections of the buildings. Appropriate fire drills and alarm tests will be carried out and the results recorded.

3.7.4 Site Accommodation

The site accommodation will be provided with adequate fire extinguishers. These will be positioned inside the accommodation and should only be used in an emergency. Where site accommodation is within the building or within 6m of a building then fire detection equipment shall be installed.

3.7.5 Maintenance of Fire Equipment

The Managing Director will ensure appropriate maintenance contracts are in place for the maintenance, testing and inspection for the various fire systems and fire extinguishers. They will also ensure fire/evacuation drills are carried out and any necessary records updated.

3.8 RISK ASSESSMENTS

Total Construction Ltd shall carry out site specific Risk Assessments for all activities carried out by the Company's employees. All personnel including employees, subcontractors and members of the public will be considered in the risk assessment procedure. While carrying out the risk assessment we will consider the hazards (something with a potential to cause harm) and the risks (likelihood of the accident happening and severity of injury or harm). The procedure to be used is based on a scale of Low, Medium or High considering likelihood and severity to calculate the risk factor.

Where high risks cannot be mitigated sufficiently by workplace precautions, a safety method statement, detailing in sequence, the safe system of work to be followed, will be produced.

Subcontractors are required to provide their risk assessments and method statements to Total Construction Limited for review and comment. These documents shall be used to monitor subcontractor performance on site.

3.8.1 Health Surveillance

Total Construction Limited will always seek to eliminate or reduce the risks to health from noise, hazardous substances and vibration and will give consideration to health surveillance as a method of risk control when necessary.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 15 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

3.9 ELECTRICITY

All reasonable steps will be taken to secure the health and safety of employees who use, operate or maintain electrical equipment. The company acknowledges that work on electrical equipment can be hazardous and it is therefore the company's intention to reduce the risk as far as is possible.

The implementation of this policy requires the total co-operation of all members' of management and staff, as well as any contractors employed to carry out work involving electrical systems and/or equipment.

Where a problem arises related to electricity at work employees must inform their Manager immediately and the Company will then take the necessary measures to investigate and remedy the situation.

Total Construction Ltd will:

- a) Ensure that electrical installations and equipment are installed in accordance with the IEE (Institute of Electrical Engineers) Wiring Regulations (BS7671)
- b) Ensure that portable equipment is inspected and tested as frequently as required to maintain it in a safe condition (the frequency will depend on the environment in which the equipment is used and the conditions of usage, i.e. how carefully it is handled)
- c) Forbid live working on any Total Construction Ltd project recognising that electrical testing/commissioning has to be dealt with separately.
- d) Forbid all work by the Company's staff on electrical equipment, unless they are competent to do so.

Temporary wiring must be as safe as a permanent installation and must be installed and tested by a competent person before being put into service and then be re-tested every three months.

3.10 WORK EQUIPMENT

All Total Construction Limited plant will be inspected weekly by the site manager (or his delegated responsible person) and the results entered into the Site Plant Inspection Register. The site manager will be responsible for ensuring all plant is maintained and repaired where necessary. Hired equipment will be subject to the same controls, as Company owned. At no time will plant or equipment be borrowed or loaned out.

Subcontractors will be monitored by the Contracts Manager and site manager to ensure that they inspect and maintain their plant in a safe condition.

Evidence of appropriate operator training and plant inspection records shall be made available by the sub contractor to Total Construction Limited.

3.10.1 Abrasive Wheels

Only personnel trained in the mounting of abrasive wheel shall mount the wheels. Training records for those appointed to change abrasive wheels are kept at Head Office.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 16 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

3.11 PERSONAL PROTECTIVE EQUIPMENT (PPE)

A standard issue of suitable PPE will be provided to all employees where the need is identified through risk assessment. Any reduction in the standard of PPE required on site must be supported by a risk assessment completed by the site manager and reviewed on a weekly basis.

Additional items of personal protective equipment will be provided for those employees who may have to work in inclement weather and hazardous situations where the risk cannot be reduced by other means.

All employees must use and wear the personal protective equipment that has been provided in order to fulfil their legal responsibilities and they are required to take reasonable care of it. Facilities for the storage of PPE will be made available within cabins provided at our sites/projects. If PPE becomes damaged, worn out or lost this should be reported to the Site Manager/Site Foreman so that replacement PPE can be provided.

3.12 WORK BELOW GROUND

Prior to any work below ground being undertaken information will be gathered about the possible presence of buried services. Where services are identified these will be marked in a way that will remain clearly visible whilst excavating is ongoing. In addition, a CAT scan is to be carried out and the scanner maintained on site for regular checking as the works proceed.

If work below ground is required near buried services this will be done in accordance with HSE Guidance document HSG47 – Avoiding Danger from Underground Services.

Information will also be obtained regarding the ground conditions to check for instability, contamination, water courses etc.

Adequate means of access and egress will be afforded to all excavations and this will be checked each week as part of the statutory inspection of the excavation.

3.13 CONFINED SPACES

Consideration will be given to alternative methods of working prior to putting staff and sub contractors to work in confined spaces.

Work in confined spaces will only be undertaken by suitably trained and competent persons. A safe system of work must be developed and agreed before the work commences and this will include procedures for dealing with emergency evacuation from the confined space.

3.14 LIFTING OPERATIONS

Lifting operations using a crane will be planned and undertaken under a contract lift arrangement.

Where lifting equipment is to be used evidence of testing and inspection will be obtained by the site manager before the equipment is put into use.

The lifting equipment selected must be appropriate for the planned lifting operation and used in conjunction with suitable slings, chains, etc.

Only personnel who are trained and authorised will act as banksmen/slingers for lifting operations.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 17 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

3.15 SITE TRAFFIC MANAGEMENT

When establishing a new site consideration will be given to the arrangements for deliveries of materials and collection of skips etc. with the intention of reducing risk associated with vehicle movements particularly reversing vehicles.

Where assistance is to be provided by us in vehicle movements the operative(s) shall wear high visibility clothing that must be clean. A risk assessment shall be completed for each site where deliveries/collections are to be made from the road and there is a risk from moving vehicles.

3.16 WORK IN OCCUPIED PREMISES

Work in occupied premises will be carried out in accordance with the appropriate statutory provisions, taking into account the safety of the occupants, who may not be aware of the hazards from the work being undertaken, in particular;

- Noise
- Use of portable electrical equipment
- Health hazards
- Alterations to fire exit routes
- Use of access equipment
- General housekeeping

Channels of communication will be set up with building occupiers and where practicable access to working areas prevented.

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 18 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016

SECTION 4 SAFETY MANAGEMENT SYSTEM

In addition to this Health and Safety Policy the Company has developed a Safety Management System to provide information and guidance to staff at all levels.

The contents of the Safety Management System include the following Safety Operating Procedures (SOP's)

Section 4 of The Companies Health and Safety Policy has developed a Safety Management System to provide information and guidance to staff at all levels.

The contents of the Safety Management System include the following Safety Operating Procedures (SOP's)

Safety Operating Procedure	HS Form No.
SOP 01 Site Induction	HS 01 rev 04
SOP 02 Monitoring Health and Safety Performance	HS 02
SOP 03 Risk Assessment	HS 03
SOP 04 Incident Reporting	HS 04
SOP 05 Construction Phase Plans	
SOP 06 Safety Method Statements	HS 06
SOP 07 Inspection of Plant and Equipment	HS 07
SOP 08 Waste Disposal	
SOP 09 Training Needs Analysis	HS 09 rev 01
SOP 10 Work at Height	
SOP 11 Display Screen Equipment	HS 11
SOP 12 Asbestos	
SOP 13 Hazardous Substances	
SOP 14 Manual Handling	HS 14
SOP 15 Vibration	
SOP 16 Personal Protective Equipment	HS 16
SOP 17 First Aid	
SOP 18 Sub Contractor Management	HS 18 rev 01
SOP 19 Temporary Works	
SOP 20 Lifting Operations	
SOP 21 Demolition	
SOP 22 Noise	
SOP 23 CDM Regulations	
SOP 24 Non English Speaking Workers	
SOP 25 Legal and Other Requirements	
SOP 26 Hot Works	HS 26
SOP 27 Tubular Scaffold	

This is a controlled document – Printed copies are void after 30 days. Print date: 22/02/17

Document No	OHS Policy	Location	TCL server	Issue No	2
Controller	N Baker			Page No	Page 19 of 19
Approved by	G Butler	Review date	March 2017	Issue date	April 2016